Notes

- 1) Centres are to complete dimensions details to suit locality
- 2) All items with red borders are to be pre-fixed prior to assessment
- 3) Steel conduit must set down to saddle from trunking
- 4) Trunking bend may be pre-manufactured
- A) Tray is to set down to be flushed with wall at this point
- B) Pre-fixed tray support brackets to space tray off wall by a minimum of 15 mm
- C) Running coupler to allow join to fixed item
- D) Conduit to terminate in DB at side or top depending on space restrictions